

VATVA INDUSTRIAL ESTATE INFRASTRUCTURE DEVELOPMENT LIMITED

C/o. Vatva Industries Association, COE Bldg, Plot No. - 511, Phase - 4, GIDC Vatva, Ahmedabad - 382445.

Name of Work : Repairing & Resurfacing of Asphalt Roads in Vatva GIDC Estate, Ahmedabad.

ટેન્ડર નોટીસ તા. 26.01.2022

SCHEDULE

It. No.	Description of Item (Brief specification to book of specification)	Approx. Qty. (Estimated)	Rates	Unit	Total Amount According to estimated Qty.
			In Figures Rs.		
1	Clearing the Site before laying of Hotmix material	50988.58		Sqm.	0.00
2	Providing cutting of existing bituminous surface upto suitable depth in line and alignment using Mechanically operator cutter machine before excavating existing surface for utility laying including cost of all type of machinery, fuel, labour, etc and as per direction of Engineer Incharge .	1635.48		Cmt.	0.00
3	Earthwork in cutting including preparing the slope and camber and stacking or utilising the cutting stuff in bank as directed upto 200 Meters from the end of cutting with all lead and lift.	1628.06		Cmt.	0.00
4	Rolling and consolidation using vibratory road roller 8 - 10 tonne capacity (incl. watering) (A) Earth work (layer not exceeding 200mm thickness).	14340.00		Sqm.	0.00
5	Providing and laying, Spreading Granular materials in required proportion so as to have mix material gradation of GSB grade II, including spreading in uniform thickness, rolling with vibratory roller 80-100 kN static wt. to proper grade and camber including watering etc. complete.	541.00		M.T.	0.00
6	Providing, laying, spreading and compacting graded stone aggregates to Wet Mix Macadam as per MORT & H specification including premixing the material with water at OMC in mechanical mix plant, carriage of mixed material by tippers to site, laying in uniform layers Manually in sub base / base course on well prepared surface and compacting with vibratory roller of 80 to 100 KN static weight to achieve the desired density.	5410.88		M.T.	0.00
7	Providing & Applying Coat, Using SS1 Emulsion Bitumen at the Rate 6.00 Kg/10smt on Water bound Macadam/WMM Surface including cleaning the surface etc. Completed.	14340.00		Sqm.	0.00
8	Scarifying gravelled macadam or Bitumen macadam surface 6 cm to 10 cm depth including stacking useful materials on road side and disposing off remaining stuff.	50988.58		Sqm.	0.00
9	Providing and spreading tack coat using Bitumen VG30 on road surface before laying hotmix material including heating the bitumen and labour charges for applying bitumen on road surface at the rate 2.5 kg/ 10 smt. with carting on site etc. comp as directed by engg. in charge. (Never Use Tyre / Plastic Material for heating the Bitumen)	64404.00		Sqm.	0.00

VATVA INDUSTRIAL ESTATE INFRASTRUCTURE DEVELOPMENT LIMITED

C/o. Vatva Industries Association, COE Bldg, Plot No. - 511, Phase - 4, GIDC Vatva, Ahmedabad - 382445.

Name of Work : Repairing & Resurfacing of Asphalt Roads in Vatva GIDC Estate, Ahmedabad.**ટેન્ડર નોટીસ તા. 26.01.2022****SCHEDULE**

It. No.	Description of Item (Brief specification to book of specification)	Approx. Qty. (Estimated)	Rates	Unit	Total Amount According to estimated Qty.
			In Figures Rs.		
10	Providing and laying DENSE GRADED BITUMINOUS MACADAM (DBM) as per gradation and bitumen for mixing shall be as arrived from mix design, provided in no case it shall be less than 4.0% for Grade I and 4.5% for Grade II by wt. of total mix as binder by batch mix type hotmix plant and laying by sensor paver finisher including consolidation by rollers as specified including providing and operating plant, sensor paver and machinery, cost of fuel, oil lubricant and labour charges including cost of aggregate and filler (If found required as per mix design)etc complete (But including cost of providing bitumen and applying tack coat emulsion).	5413.84		M.T.	0.00
11	Providing and laying 25mm to 50mm thick compacted BITUMINOUS CONCRETE (BC) using aggregates as per gradation and percentage of bitumen for mixing shall be as arrived from mix design, provided in no case bitumen percentage shall be less than 5.0% for Grade I and 5.6% for Grade II by Wt. of total mix as binder by batch mix type hot mix plant and laying by sensor paver finisher including consolidation by rollers as specified including providing and operating plant, sensor paver and machinery, cost of fuel, oil, lubricant and labour charges, tests required to be carriedout including cost of aggregate and filler (if found required as per mix design) etc. complete (But including cost of providing bitumen and applying tack coat emulsion).	4984.13		M.T.	0.00
12	Providing and Appling Asphalt Painting on BT surface with Bitumen VG-30 at rate of 6.00 kg/10 smt by Mechanical Sprayer & Spreading of Stone Dust on painting surface of road @ 0.03 cum/10 smt with brooming etc. complete as directed.	50988.58		Sqm.	0.00
Total Rs.					

(A) Total Tendered Amount :**Signature of Contractor**

વટવા ઈન્ડસ્ટ્રીયલ એસ્ટેટ ઈન્ફ્રાસ્ટ્રક્ચર ડેવેલપમેન્ટ લિમિટેડ

ટેન્ડર નોટીસ તા. 26.01.2022

-:કામની શરતો:-

- 1) આ કામ માટે કોન્ટ્રાક્ટર 'A' અથવા 'AA' કેટેગરી નું રજીસ્ટ્રેશન હોવું જરૂરી છે.
- 2) ઉપર જણાવેલ આઈટમોની અંદાજિત ક્વોટીટી છે જેમાં વધ-ઘટ થઈ શકે છે
- 3) રોડના ઓજીએલ લઈ પ્રોફાઈલ બનાવી એફઆરએલ આજુબાજુના રોડ સાથે મેચ કરી લેવલ કરી, ફિક્સ કરી, સેન્સર પેવરથી કામગીરી કરવાનું રહેશે.
- 4) ડામર કામની આઈટમમાં VG-30 ડામર વાપરવાનો રહેશે જેનો બેઝિક સ્ટાર IOCL ના તા. 16.01.2022 મુજબ રહેશે.
- 5) જે તે સમયના બીલ માટે સ્ટાર રેટની સરખામણી તે સમયના IOCL ના ભાવપત્રક સાથે કરી, તે મુજબ ડામરના ભાવમાં વધારો અથવા ઘટાડો ચૂકવવામાં આવશે.
- 6) ઈએમડી રૂ. 100000/- (અંકે રૂ. એક લાખ) નો ડીડી Vatva Industrial Estate Infrastructure Development Limited ના નામનો ભાવપત્રક સાથે આપવાનો રહેશે.
- 7) આ કામ માટે જે તે કોન્ટ્રાક્ટરનું ટેન્ડર સ્વીકારવાની તથા મંજૂર કરવાની અબાધિત સત્તા ચેરમેન, વટવા ઈન્ડસ્ટ્રીયલ એસ્ટેટ ઈન્ફ્રાસ્ટ્રક્ચર ડેવેલપમેન્ટ લિમિટેડને રહેશે અને તેમાં કોઈ વાંધો લઈ શકાશે નહીં.
- 8) આ ટેન્ડર ભરનારે છેલ્લા 5 વર્ષમાં આસ્ફાલ્ટ રોડના એવરેજ 5 કરોડના કામ કરેલ હોવા જોઈએ તથા તેની વિગતો આપવાની રહેશે.
- 9) આ કામ દરમ્યાન દરેક બિલના 5% રકમ સિક્યોરિટી ડિપોઝીટ તરીકે વટવા ઈન્ડસ્ટ્રીયલ એસ્ટેટ ઈન્ફ્રાસ્ટ્રક્ચર ડેવેલપમેન્ટ લિમિટેડમાં જમા રહેશે. જે સંપૂર્ણ કામ પૂરું થયે પરત કરવામાં આવશે.
- 10) બેરીકેડ તથા જરૂરી સેફ્ટી પ્રિકોશનની તમામ જવાબદારી કોન્ટ્રાક્ટરની રહેશે
- 11) મટીરિયલ ટેસ્ટિંગ કોન્ટ્રાક્ટર ના ખર્ચે કરવાનું રહેશે અને તેના પરિણામ મુજબ ચૂકવણું થશે.
- 12) આ કામ દરમ્યાન કોઈપણ વસાહતની માળખાકીય સુવિધાને નુકશાન થશે તો તેનું રિપેરિંગ કોન્ટ્રાક્ટરે સ્વખર્ચે કરાવવાનું રહેશે.
- 13) આપના ભાવ સીલબંધ કવરમાં રજૂ. એડી અથવા રૂબરૂમાં તા.03.02.2022 સુધીમાં ઓફિસ સમય દરમ્યાન મોકલી આપવા.